Resources

Full specifications are published on the project specification portal and are updated quarterly. Contact the project office for printed copies.

Section two describes the inspection regime. Each delivery is inspected on arrival by a qualified representative, who records the condition of packaging, the quantity received, and any visible damage. Materials found defective are rejected and returned at the expense of the contractor, and replacement materials must arrive within ten days.